

Steel Truck Actuated Dock Leveler Front of Dock 6 Ft. Length 20000 Lb. Capacity Brown

MODEL PU-600-SCB

Loading Dock Equipment / Truck Actuated Dock Levelers



PRODUCT OVERVIEW

This is a fully automatic loading ramp where there is no dock attendant needed. It is a dock leveler unit with legs for in front of dock placement. It consists of a lift by-pass for safety and toe guards on each side. As the truck backs against the twin actuating arms (bumpers) it pushes the carriage back. The dock and trailer must be raised for this process to work. As the carriage goes back the deck goes up. When the carriage bumpers contact the dock, the deck floats down to rest on the trailer. When the truck pulls out, the deck returns to level supported position automatically. Please specify dock height when ordering.

KEY FEATURES

- Fully-automatic loading ramp where no dock attendant needed
- Dock leveler unit with legs for in front of dock placement for ideal use
- Consists of a lift by-pass and toe guards on each side for optimal safety
- Deck returns to level supported position automatically

CORE PRODUCT DATA

ASSEMBLED WEIGHT
2394 lbs

ASSEMBLED SIZE
88" W x 85.25" L x 50.875" H

SHIP WEIGHT
2394 lbs

PACKAGE 1 SIZE
86" W x 86" D x 55" H

COLOR / FINISH
Brown

FREIGHT TYPE
Parcel

AVAILABILITY Please Contact Vestil for Current Availability

QUICKSHIP: --

Products are sold through Vestil distributor partners. Contact a distributor for current pricing and ordering.

PRODUCT SPECIFICATIONS

Uniform Capacity (lb.)	20,000
Molded Bumper Width (in.)	5
Molded Bumper Height (in.)	16
Molded Bumper Depth (in.)	2
PSI Checker Plated Deck	55,000
Service Range Above Dock (in.)	12
Service Range Below Dock (in.)	8
Long Lip (in.)	12 (extends 6-1/2 (in.) into truck)
Deck Width (in.)	72
Deck Length (in.)	72
Platform Thickness (in.)	1/4

PRODUCT & SHIPPING REFERENCE

Shipping Point: Angola, IN 46703

Warranty: 1 Year

AVAILABLE PRODUCT RESOURCES



SCAN FOR CURRENT PRODUCT DATA